


Key

- ① Existing structural deck
- ② Existing Decothane surfaces; thoroughly clean the area around every proposed penetration/application area using conventional means, rinse thoroughly to avoid residues and allow to dry
- ③ Proprietary photovoltaic fixing bracket by others
- ④ Sika Liquid Plastics Reactivation Primer applied in a minimum 200mm border around each bracket
- ⑤ Sika Metal Primer applied applied on to exposed metal surfaces; galvanised metals must be treated with mordant solution before priming
- ⑥ Sika Flexistrip applied on to bolt heads to ease application and embedment of Reemat Premium
- ⑦ Decothane Base Coat applied at 1.0l/m² with embedded Sika Reemat Premium 150mm beyond bracket positions
- ⑧ Decothane Top Coats as per ORIGINAL Sika Liquid Plastics Project Specification in a minimum 175mm [Base Coat must not be left exposed to UV]
- ⑨ Heavy duty tie wrap or O-clip applied to the exposed edge of waterproofing



Sika Liquid Plastics
 Sika House
 Miller Street
 Preston
 Lancashire PR1 1EA
 Telephone: 01772 259781
 Email: technical.customer.services@uk.sika.com
 Web: www.liquidplastics.co.uk

This drawing is solely intended to illustrate the correct application of Sika Liquid Plastics products and systems. It must be read in conjunction with the appropriate specification and current issue of relevant Product Data Sheets. All elements bearing reference to structural and/or thermal design are shown indicatively and should not be used in whole or in part for any aspect of project design without consulting the relevant authorities.

For refurbishment projects, all aspects of the existing roof are deemed to be fully compliant with BS 6229:2003 [Code of Practice for Flat Roofs with Continuously Supported Coverings] or improved upon for instances where these standards are not met.

Site-specific details not covered by our standard range can be obtained by providing relevant information to the email address shown.

Project No	
DWG No	Revision
Project:	
Drawing Title: Waterproofing Termination Detail to a typical photovoltaic mounting bracket	
Scale: NTS @ A3	Drawn:
Date:	

